

Ceiling Fixing: IST delivery model

IST ref: CF

16-week programme

Subject	No. of weeks	Content		
Pre-arrival				
Sign up with CITB Apprenticeship Officer	_	Sign up, Travel, Expenses, Accommodation (As required)		
Block 1: Weeks 1-2				
Induction	2	Site induction; study skills; HSW basics (HASAWA, WHR, asbestos, manual handli ng , noise and vibration, fire awareness, COSHH); PPE/RPE; occupational health; small tools/equipment; storage principles Health and Safety; RAMS; Portfolio development; Introduction to SVQ, Induction to practical training		
Remote, independent and work-based learning		Onsite Practical training and Experience		
Block 2: Weeks 3-4				
Tools and Equipment	1	Introduction to Power Tools, Abrasive wheels, Small Plant, Maintenance. Systems of work. Theory and Practical Training sessions. Literacy and Numeracy.		
Introduction to ceilings	1	Lay-in Ceilings, Systems, tiles, fixing. Theory and practical task. Literacy and Numeracy.		
Remote, independent and work-based learning	-	Onsite Practical training and Experience		
Block 3: Weeks 5 - 6				
Technology	1	Scale rules, Graphical symbols and drawings, Construction technology, Communications, Standards Tolerances. Theory and Practical, Literacy and Numeracy		



1	Measuring, cutting, levelling, fixing grid systems Theory and Practical training sessions. Literacy and Numeracy. Move handle and store resources. Practical and Theory sessions.		
-	Onsite Practical training and Experience		
1	Measuring, cutting, levelling, fixing grid systems Theory and Practical training sessions. Literacy and Numeracy Practical and Theory sessions. Assessments		
1	Measuring, cutting, levelling, fixing grid systems Theory and Practical assignments. Literacy and Numeracy. Practical and Theory sessions. Assessments		
-	Onsite Practical training and Experience. SVQ Portfolio Gathering Evidence		
Block 5: Weeks 9 - 10			
1	MF systems, measuring, cutting, fixing, Types of sheet materials/boards, methods of installation fixing. Theory and practical training, literacy and numeracy.		
1	MF systems, measuring, cutting, fixing, Types of sheet materials/boards, methods of installation fixing. Theory session and practical assignments, literacy and numeracy.		
-	Onsite Practical training and Experience. SVQ Portfolio Gathering Evidence. Submitting evidence for review.		
Block 6: Weeks 11 - 12			
1	MF systems, measuring, cutting, fixing, Types of sheet materials/boards, methods of installation fixing. Theory session and practical assignments, literacy and numeracy. Assessment.		
1	Introduction to metal pan ceilings, Measuring, cutting, levelling, fixing grid systems Theory and Practical training sessions. Literacy and Numeracy. Practical and Theory sessions.		
	1 1 1 1		



Remote, independent and work-based Learning	-	Onsite Practical training and Experience. SVQ Portfolio Gathering Evidence. Submitting evidence for review.		
Block 7: Weeks 13 - 14	Block 7: Weeks 13 - 14			
Installing metal pan ceilings	1	Fixing metal pan ceilings, Measuring, cutting, levelling, fixing grid systems. Theory and Practical training sessions. Literacy and Numeracy. Practical assignments and Theory sessions.		
Installing metal pan ceilings	1	Fixing metal pan ceilings, Measuring, cutting, levelling, fixing grid systems. Theory and Practical training sessions. Literacy and Numeracy. Practical assignments and Theory sessions. Assessments		
Remote, independent and work-based Learning	1	Onsite Practical training and Experience. SVQ Portfolio Gathering Evidence. Submitting evidence for review.		
Block 8: Weeks 15 - 16				
Installing linear strip ceilings	1	Fixing linear strip ceilings, Measuring, cutting, levelling, fixing grid systems. Theory and Practical training sessions. Literacy and Numeracy. Practical assignments and Theory sessions. Assessments		
Fire Barriers	1	Rockwool, fire fly systems, theory methods of fixing practical assignments, assessment.		
Work-based SVQ Assessement	_	Onsite Practical training and Experience. SVQ Portfolio Gathering Evidence. Submitting evidence for Assessment.		