

## Standard ref: ST0388

## 18-week programme

## Interior Systems: Framework delivery model

Subject	No. of weeks	Content	
Pre-arrival, L1 to be con		o college enrolment	
Functional skills		Induction	
		L1/L2 Literacy	
		L1/L2 Numeracy	
Block 1: 2 weeks			
Health and safety	1	Health and safety training: working at height (towers and	
		MEWPs), RAMS, asbestos awareness, manual handling,	
		PPE, occupational health and environmental factors;	
		spaced learning exercise; hand and power tool use	
Building principles	1	General principles of building design: fire, noise,	
		vibration, air and water barrier requirements and	
		regulations; interpreting drawings and construction	
		information	
Remote, independent	-	Levelling up of functional skills; levelling up of study	
and work-based		skills; weekly completion of site diary; regular	
learning Block 2: 4 weeks		performance review with employer	
	1	Coloulating quantities using a range of information	
Basic quantities calculation	I	Calculating quantities using a range of information	
Plasterboard partitions	1.5	sources Construct metal stud partitions (solid module); setting	
Plasterboard partitions	1.5	out: materials, tools, equipment, resource knowledge and	
		skills	
Metal frame ceilings	1.5	Construct metal frame ceilings, including bulkheads and	
Metal frame centrigs	1.5	access panels	
Remote, independent	-	Weekly completion of site diary; regular performance	
and work-based		review with employer	
learning   Block 3: 4 weeks			
Drylining partitions 1	1.5	Construct partitions, including junctions and openings;	
		different types of drylining partitions: overboard height,	
		service shaft, curved walls, staggered stud	
Drylining partitions 2	1.5	Construct partitions, including deflection details and	
		repairs; setting out: materials, equipment, resource	
		requirements	
Linings and	1	Construct framed wall linings; GypLyner: fixing types and	
encasements 1	•	substrate requirements	



Remote, independent and work-based learning	-	Weekly completion of site diary; regular performance review with employer	
Block 4: 4 weeks			
Linings and encasements 2	1	Construct framed wall linings (metal/timber stud), including openings; framed and frameless beam encasements	
Suspended ceilings 1	2	Construct suspended ceilings, including tiles, pattresses and upstand details; materials, resources and equipment requirements; hanger systems	
Suspended ceilings 2	1	Construct suspended ceilings (metal clip-in); materials, resources and equipment requirements	
Remote, independent and work-based learning	-	Weekly completion of site diary; regular performance review with employer	
Block 5: 4 weeks			
Demountables 1	1	Construct composite partitions, including openings, doors, glazing and finishes	
Demountables 2	1	Construct stud and board partitions, including openings, doors, glazing and finishes	
Preparation and recap for assessments; Enrichment 1	1	Recap, practice and preparation; enrichment activities (practical skills)	
Preparation and recap for assessments; Enrichment 2	1	Recap, practice and preparation; enrichment activities (higher study)	