

Steelfixer: Framework delivery model

Standard ref: ST0271 18-week programme

Subject	No. of weeks	Content	
Pre-arrival, L1 to be complete prior to college enrolment			
Functional skills	_	L1/L2 Literacy	
		L1/L2 Numeracy	
Block 1: 2 weeks			
Health and safety training	1	HASAWA 1974; PUWER; LOLER; COSHH; general site	
		safety; spaced learning; Prevent training	
	1	Glossary of terms used; types and quality of steel	
Steelfixing fundamentals		available; traceability; good practice standards;	
		fundamental aspects of purpose, use and interpretation	
		of drawings and schedules	
Block 2: 4 weeks			
Levelling and setting out	1	Instruments and techniques in LSO; LSO practices	
(LSO)			
Steelfixing practical		Bar selection; marking out and setting out; referencing	
exercise: basic floor slab,	1	simple drawing; correct use of spacers and use of	
basic wall		temporary bars for stability; using different ties as	
		appropriate	
Steelfixing practical	1	Compression and cantilever beams, using simple links	
exercise: basic beam cage		and stirrups, ties and temporary bars for stability	
Slinger/signaller	1	Safe lifting techniques; resources/prefabricated elements	
Abrasive wheels Mobile towers		Use of abrasive wheels	
		Safely erect and use mobile tower	
Block 3: 4 weeks			
Steelfixing practical exercise: basic column	1	Prefab round and square/rectangular columns Prefab pile cages	
fabrication, pile cage and		Prefab and in-situ pile caps	
pile caps		1 Total and in old pile dape	
Construction technology,	1	Traditional and modern construction methods;	
information and		technology and systems of work in different industry	
communication 1		sectors	
Steelfixing: cutting and	1	Methods of cutting rebar; tolerances; bending rebar by	
bending and joining		mechanical means (hand and power benders); correct	
		use of formers; rebar couplers	
Steelfixing practical	1	Assemble ground beams with beamform; place and	
exercise: ground beams		securely fix anchor bolts; place column starters/upstands	
with beamform, anchors			
and features			



Block 4: 4 weeks		
Construction technology,	1	Building information modelling (BIM); drawings; methods
information and		of communication; environmental factors; contaminated
communication 2		ground
Steelfixing practical	1	Accurate marking out and fixing in-situ of cut-
exercise: floor slab with		outs/apertures, column and wall starters, upstands
Features		
Steelfixing practical	1	Doorways; typical corners; sloping walls
exercise: walls with		
features		
Preparation and recap for	1	Recap, practice and preparation; enrichment activities
assessments; Enrichment 1		(practical skills)
Block 5: 4 weeks		
Steelfixing practical	1	Complex column fabrication; mock synoptic
exercise: column		
fabrication		
Steelfixing practical	1	Pile cap fabrication; beam fabrication; mock synoptic
exercise: pile cap		
fabrication and beam		
fabrication		
Steelfixing practical	1	Wall construction in-situ; mock synoptic
exercise: wall construction		
in-situ		
Preparation and recap for	1	Recap, practice and preparation; enrichment activities
assessments; Enrichment 2		(higher study)